

PRICE QUOTATION  
**MURRAY SHEET METAL CO., INC. WV #6**  
3112 7TH STREET - PARKERSBURG, WEST VIRGINIA 26101  
(304) 422-5431 - FAX: (304) 428-4623

TO:	<b>WOOD COUNTY COMMISSION</b>	Date: 9/7/2023	Please indicate this number when ordering: <b>2023-AM-070</b>
	<b>Attn: TODD NONAMAKER</b>	Inquiry Dated:	Terms: NET 30
		Proposed Shipping Date:	To be shipped via: MURRAY TRUCK
		Salesperson: Alex McCay	FOB: JOBSITE

**HERE IS OUR QUOTATION ON THE GOODS NAMED, SUBJECT TO THE CONDITIONS NOTED:**

**CONDITIONS:** The price and terms on this quotation are not subject to verbal changes or other agreements unless in writing by the Home Office of the seller. All quotations and agreements are contingent upon strikes, accidents, fires, availability of materials, and all other causes beyond our control. Prices are based on costs and conditions existing on the date of quotation and are subject to change by the seller before final acceptance. Typographical and stenographic errors subject to correction. The purchaser agrees to accept either overage or shortage not more than ten percent to be changed for pro-rata. Purchaser assumes liability for patent and copyright infringement when goods are made to Purchaser's specifications. When a quotation specifies material to be furnished by the purchaser, ample allowance must be made for reasonable spoilage and material must be of suitable quality to facilitate efficient production. Conditions not specifically stated herein shall be governed by established trade customs. Terms inconsistent with those stated herein which may appear on purchaser's formal order will not be binding on the seller. **The retainer will be paid within 60 days of invoice submission and completion of our work, and not subject to "pay when paid" conditions in the contract with the owner.**

**ROOF OVERLAY PROPOSAL – 211 SIXTH ST, PARKERSBURG, WV  
APPROX 6,300 SQFT**

We propose to furnish material, equipment, labor, and supervision to perform the following  
Scope of work:

- 1) Remove and dispose of existing base flashings and metal trim. Any masonry that is damaged during demolition will be repaired/replaced on a time/material basis. Existing roof system to remain.
- 2) Furnish and mechanically fasten ½" HD Coverboard to the entire roof area.
- 3) Furnish and fully adhere .060" EPDM membrane to the entire roof area. All penetrations and terminations are to be flashed per manufacturer's specifications.
- 4) Fabricate and install new gravel stop edge metal, gutter and downspout at penthouse roof and main roof.
- 5) Replace wood blocking beneath condenser units.
- 6) Price includes building permit, B&O taxes, and a 20-year manufacturer's warranty.

Complete for the total of **\$91,116.00**

Alternate: Sand, prime and paint (11) Chimney Caps **add \$2,439.00**

**EXCLUSIONS:** Bonds – Coping at stone parapet – Demolition of existing roof system – Hazardous abatement – Masonry Repairs – Decking repairs/replacement.

QUOTE VALID FOR \_\_\_\_\_ DAYS.

BY \_\_\_\_\_

WHITE/ORIGINAL - CANARY/DUPLICATE - PINK/TRIPPLICATE

TO CONFIRM ORDER, SIGN AND RETURN WHITE ACCEPTANCE COPY